



QUOTATION

Rescue 1 Stock 12'6"
 Chad Newsome
 2201 Atlantic Avenue
 Manasquan, NJ 08736
 732-223-1411
 732-223-8456
 cnewsome@plcustom.com

Rescue 1 Stock 12'6"
 Chad Newsome
 2201 Atlantic Avenue
 Manasquan, NJ 08736
 732-223-1411
 732-223-8456
 cnewsome@plcustom.com

Exp. Date: 03/30/2025
Quote No: R375-0005
BODY: 126LD 12'6 Light Duty

04/15/2026

PART NO	S	DESCRIPTION	QTY	ID
== 12'6 Light Duty - 34.100 01/27/25 ==				
RESCUE 1 -(New Units)				
00-00-0085		-----Created with QW Ver. 10 Software-----	1	PL
00-00-0100		Rescue 1 - New Units - Release 34.39 effective 1/6/2026	1	PL
DIMENSIONAL REQUIREMENTS				
00-20-0000	< >	CRITICAL DIMENSIONS	1	PL
		The customer has requested the following MAXIMUM vehicle dimensions:		
		Maximum permissible vehicle length: UNKNOWN		
		Maximum permissible vehicle height: UNKNOWN		
		Building bay height: UNKNOWN		
		Grade of driveway entering building bay: UNKNOWN		
00-20-0060	< >	Overall vehicle dimensions	1	PL
		Overall vehicle length: 29' +/- 2"		
		Overall vehicle height: 8' - 8" +/- 2"		
00-20-0600	<	Dimension tolerance statement	1	PL
		All dimensions within this specification are approximate.		
		All compartment dimensions are clear opening.		
BODY TYPE				
00-21-1200	>	Non Walk In, 12'-6", Light Duty	1	PL
00-45-2000	<	Body 96" Wide	1	PL
		Overall vehicle width: 8' - 4"		
BODY CONSTRUCTION				
03-00-1090	< >	Chassis Type -Ford F-Series (Crew Cab)	1	PL
		Chassis paint must be reviewed/edited when changing chassis type		
10-10-3000		Aluminum Construction, Light Duty	1	PL
10-10-5000	<	Structural Integrity Warranty	1	PL
		The structural integrity of the body shall be guaranteed for the life of the unit, as long as the original purchaser shall own it.		
10-15-5200		Body Mtg, 3" x 1" Aluminum Bar, Heavy Duty	1	PL
10-30-1000		Exterior Fasteners	1	PL
10-40-2200	>	Front Skirt Length of Body 28.25", 6" drop skirt, Heavy Duty	1	PL
ROOF CONSTRUCTION				
10-50-1500	>	Roof, Aluminum Diamond Plate, .125"	1	PL
EXTERIOR COMPARTMENT DOORS				
11-40-3610	<	Amdor Roll Up Doors, Anodized, Locking	7	PL
		Locks to use type T001 keys.		

PART NO	S	DESCRIPTION	QTY	ID
COMPARTMENT CONSTRUCTION AND CONFIGURATION				
12-L1-0110	<	Compartment L1, Left Side, 81h x 49w x 26d COMPARTMENT L-1: Left Side, Compartment transverse above chassis frame. Due to Spring Shackle & Brake Cable the Compartment Depth below Floor Frame is 19".	1	PL PL
12-L2-0110	<	Compartment L2, Left Side, 51h x 46w x 26d COMPARTMENT L-2: Left Side.	1	PL
12-L3-0110	<	Compartment L3, Left Side, 75h x 38w x 26d COMPARTMENT L-3: Left Side. Due to Spring Shackle the Compartment Depth below Floor Frame is 18". Above chassis frame the depth is 26".	1	PL
12-R1-0110	<	Compartment R1, Right Side, 81h x 49w x 26d COMPARTMENT R-1: Right Side, Compartment transverse above chassis frame. Due to Spring Shackle the Compartment Depth below Floor Frame is 19".	1	PL
12-R2-0110	<	Compartment R2, Right Side, 51h x 46w x 26d COMPARTMENT R-2: Right Side.	1	PL
12-R3-0110	<	Compartment R3, Right Side, 75h x 38w x 26d COMPARTMENT R-3: Right Side. Due to Spring Shackle the Compartment Depth below Floor Frame is 18". Above chassis frame the depth is 26".	1	PL
12-RB-0110	<	Compartment RB1, Rear, 73h x 35w x 13d COMPARTMENT RB1: Rear. Compartment Depth Below Chassis Frame is 13", above chassis frame it is 90".	1	PL
COMPARTMENT CONSTRUCTION, LIGHT DUTY				
13-00-R090		Compartment Material .125" Aluminum (Diamond Plate)	1	PL
13-30-1000		Vent Exterior Compts, 10" x 5" Diamond plate Vent	1	PL
13-40-1005		Turtle Tile, Floors of Compartment (All) Black	1	PL
13-40-2105		Turtle Tile, Shelves, Exterior Compartments, Black	1	PL
13-40-2205		Turtle Tile, Roll-Out Trays, Exterior Compartment, Black	1	PL
13-41-1120		Turtle Tile Edge Color, Black	1	PL
COMPARTMENT SHELVES ,TRAYS ,DIVIDERS LIGHT DUTY				
13-75-7R44	<	1000 LB Roll-Out Tray, Two Direction, 44" Wide, ROM L1/R1	1	PL
13-80-1000	< >	Shelf, adjustable, 3/16" Alum., 25 Deep, Custom width Quantity: 4 Location: (2) L3 , (2) R3	4	PL
13-81-8150	<	1,000 LB Roll-Out Tray, Fixed, RB1 Comp., Above frame Length restricted to 84". Use 13-81-8160 or 13-81-8155 for longer trays.	1	PL
13-84-5230	< >	Tool Board 3/16" Aluminum, Tray mounted, dual direction Qty:1 Location: L1/R1	1	PL
<		REAR BUMPER		PL
		MAXIMUM Height from Ground 24" per NFPA 1901. For Angle of departure see 00-20-0020 or 00-20-0025.		

PART NO	S	DESCRIPTION	QTY	ID
14-05-0510		Rear Bumper, 12", Recessed - 96" Wide Body	1	PL
14-07-1000	< >	Rear Bumper Receiver, Class IV Incorporated into the rear of the vehicle shall be a 2" receiver. The system shall include steel reinforced members attached to the vehicle chassis frame which extend to the rear of the vehicle. The 2" by 2" receiver shall run through the center of the rear bumper to accept a large eye bolt or SAE Class IV Tow Hitch. The system shall be designed for a 10,000 LB maximum Gross Trailer Weight. 1000 LB Trailer Tongue Weight. Note this system is not designed for weight distributing applications.	1	PL
14-10-0500	>	Tow eye, shipped loose	1	PL
EXTERIOR ACCESSORIES				
15-10-3560	< >	Front Corner Coves, Custom Color - No Diamond plate, Full Height Color of Polycoat: Job Color Red ILO Diamond Plate Stone Guard	1	PL
15-10-3860	< >	Front Body Stone Guard, (no dia plate) Polycoat, Custom Color, Full Height Color of Polycoat: Job Color RED ILO Diamond Plate Stone Guard	1	PL
15-10-5260	< >	Rear Corner Coves, Custom Color - No Diamond plate, 4" Color of Polycoat: Red ILO Diamond Plate Stone Guard	1	PL
15-20-1050		Rub-Rails, Offset bolt-on, "C" - Channel	1	PL
15-30-2300		Running Boards, Light Duty, (4) Door, Ford F-Series w/ Grip Strut	1	PL
EXTERIOR TRIM				
16-10-1600	<	Fenderettes, Rolled, Polished Stainless Steel, Light Duty 225/70R19.5 Tires	1	PL
16-10-5000		Mud Flaps rear	1	PL
16-30-1500		License Plate Holder w/LED Lt,Cast Prod Polish, Lt Side Body	1	PL
16-35-1010		Fuel Fill Housing, Cast products, Polished LT Duty	1	PL
16-36-1010		DEF Fill Housing, Cast products, Polished (F-Series)	1	PL
16-70-1000	<	Grab Rails, Rear of Body, Knurled Stainless Steel, (2) 36" Location: Two vertical rear body.	1	PL
EXTERIOR, MISCELLANEOUS				
17-50-1000		Undercoat Body	1	PL
17-75-1000	<	Upper body rigging system, four corners 1000LB WL Rigging Points meet NFPA 1901 paragraph 15.12.2 with a Factor of Safety of 9. Rigging Points are rated at a Practical Working Load of 1000 lbs in any direction.	1	PL
ELECTRICAL				
40-00-1100	< >	Electrical Panel, 12 VDC ,Location For Walkaround Trucks & Walk-In Trucks with Tranverse L1/R1, the 12 VDC Panel will be primarily located in the Forward Wall of the R1 Compartment with some 12VDC & 120VAC Components located in the Center of the Forward Wall between L1 & R1. For Walk-In Trucks the 12VDC Board & some 120VAC Components will be located above the Counter Top in the Forward Streetside (Driver's Side) area approximately 60" Long & 6" Deep. This will reduce the Couner Top Depth by 6".	1	PL
40-00-3000	<	Electrical 12 VDC, V-MUX Multiplex System - for Commercial w/Screen Includes Weldon Vista IV screen. Screen Location: Cab Console	1	PL

PART NO	S	DESCRIPTION	QTY	ID
40-00-5000	< >	Electrical System Warranty The Electrical System shall be warranted for the limited life of the unit, as long as the original purchaser shall own it. V-MUX COMPONENTS HAVE SEPARATE WARRANTY.	1	PL
	>	CAB ELECTRICAL		PL
41-30-3700		Master Switch, Ignition Controlled	1	PL
		CAB CONSOLE		PL
42-20-0500		Battery On Green Indicator light ,Console	1	PL
42-20-3500		Audible Alarm, Compartment open	1	PL
42-20-4690	<	Do not Move Warning Light,, Red OS, Console A "Do not Move" will illuminate if: (1) Any driver, passenger, or chassis equipment compartment door is not closed. (2) Any body compartment door or entrance is not closed. (3) Any ladder or equipment rack is not in the stowed position. (4) Powered light tower is not stowed. (5) Any other device permanently attached to the apparatus is open, extended, or deployed in a manner that is likely to cause damage to the apparatus if the apparatus is moved. These conditions will also activate the chassis supplied "Do Not Move" Audible Alarm if equipped.	1	PL
42-25-6000	<	High Idle Activation, Ford OEM - F-Series Activated by front console switch, requires park brake to be applied	1	PL
42-30-2000		Back-up alarm, no switch	1	PL
42-35-5000		Under Hood Work Light	1	PL
42-60-2400		Air Horn, (2) Buell 1062, bumper valance mount , 1/4 hp compressor	1	PL
42-60-4800		Air Horn activation, "Plunger Style" switch, drivers console	1	PL
42-65-1851	<	Power Door Lock Concealed Override Switch, Cab, F-Series Located in front grille.	1	PL
		EMERGENCY WARNING EQUIPMENT		PL
43-20-4G00		Siren, Whelen 295SLSA1, w/diagnostics	1	PL
43-20-5200	XS >	Siren-Horn-Air Horn Switch -VMux	1	PL
43-31-4310		Thru Bumper Speakers, CPI SAD/P 3800 Series, (2) F-Series, 2023on	1	PL
		EMERGENCY LIGHTING		PL
	>	WARNING LIGHT FLASH PATTERNS		PL
43-40-1T00	<	LED Upper Lights, Alternating Flashing Pattern Lights to flash in an alternating A-B flash pattern.	1	PL
43-40-1T20	<	LED Lower Lights, Alternating Flashing Pattern Lights to flash in an alternating A-B flash pattern.	1	PL
		FRONT LIGHT BAR		PL
43-40-6450	<	Whelen Edge Freedom IV LED Light Bar, Model F4N2VLED, 55" This is a specific Light Bar as specified in the long specification	1	PL
		ZONE A UPPER WARNING LIGHTS		PL
43-41-4105	<	Whelen M9 Series LED, Red Location: Front body. Color: Red with clear lens.	5	PL
43-41-4117	<	Whelen M9 Series LED, White Location: Front body. Color: White.	2	PL

PART NO	S	DESCRIPTION	QTY	ID
ZONE B UPPER WARNING LIGHTS				
43-42-4105	<	Whelen M9 Series LED, Red Location: Curbside body. Color: Red with clear lens.	2	PL PL
ZONE C UPPER WARNING LIGHTS				
43-43-4105	<	Whelen M9 Series LED, Red Location: Rear body. Color: Red with clear lens.	2	PL PL
ZONE D UPPER WARNING LIGHTS				
43-44-4105	<	Whelen M9 Series LED, Red Location: Streetside body. Color: Red with clear lens.	2	PL PL
ZONE A LOWER WARNING LIGHTS				
43-46-4641	<	Whelen T-Series LED, Red, Chrome Flange Location: Front. Color: Red with clear lens. Includes chrome flange.	4	PL PL
ZONE B LOWER WARNING LIGHTS				
43-47-4641	<	Whelen T-Series LED, Red, Chrome Flange Location: Curbside body. (1) Cab front fender, (1) Cab running board below "B" pillar, (1) Body rub rail Fwd, (1) Body rub rail Aft. Color: Red with clear lens. Includes chrome flange.	1	PL PL
ZONE C LOWER WARNING LIGHTS				
43-48-4305	<	Whelen M6 Series LED, Red Location: Rear body. Color: Red with clear lens.	2	PL PL
ZONE D LOWER WARNING LIGHTS				
43-49-4641	<	Whelen T-Series LED, Red, Chrome Flange Location: Streetside body. (1) Cab front fender, (1) Cab running board below "B" pillar, (1) Body rub rail Fwd, (1) Body rub rail Aft. Color: Red with clear lens. Includes chrome flange.	1	PL PL
REAR LIGHT BAR				
43-50-7800	<	Whelen Traffic Advisor, TAM85 SUPER LED, 47" Controller active with Cab Master Power.	1	PL PL
EXTERIOR VEHICLE LIGHTS -(Stop/Tail/Turn)				
44-02-0175		Exterior Vehicle Lights -WHELEN M6 - Clear Lens, Chrome Flange	1	PL PL
44-26-0150	<	Stop/Tail, (2) M6 -Whelen Super LED, Clear Lens, Chrome Flange Lights to include clear lenses and chrome flanges.	1	PL
44-26-0300	<	Back-up, (2) M6 - Whelen Super LED, Chrome Flange Lights to include chrome flanges.	1	PL
44-26-0550	<	Directional, (2) Whelen M6 Super LED Arrow, Clear Lens, Chrome Flange Lights to include clear lenses and chrome flanges.	1	PL
44-27-R036	U	Directional, (2) Whelen M6 Super LED, Arrow, Chrome Flange, Additional Front	1	
44-30-1000		LED Marker/Clearance Lights	1	PL

PART NO	S	DESCRIPTION	QTY	ID
44-30-1010		LED Marker/Clearance Lights, Amber, additional for front Body	1	PL
44-30-2000	<	Reflectors, Reflex, per NFPA Reflectors located per procedure SMP-000125	1	PL
44-30-3230	<	Addit'nl Whelen Lwr Side LED Its, Flash w/Directional-Amber w/Chrome Flange Whelen 500 Series Amber LED light w/ clear lenses and chrome flange Quantity: (2), (1) Each side in rear wheel well area.	1	PL
44-30-6050	<	Cab Step Illumination Lights, Two/Four door cab, Whelen Super LED Quantity: (2). Location: (1) Light each side on front of body facing forward over cab steps. Activate with Cab Doors Open. Whelen 2G Series.	1	PL
44-30-6100	<	Ground Illumination Lights, Chassis Doors, Whelen Super LED, 4 Door Cab Four door cab. Activate with Cab Doors Open or when body ground lights are activated if equipped with body ground lights. One Light per Door, under the Door.	1	PL
44-35-1000	< >	Rear red warning lights to activate as brake lights The upper zone "C" red emergency warning lights will function as brake lights and warning lights. LED lights shall be programmed to steady burn mode and shall flash in an 'A-B' alternating pattern in warning light mode.	1	PL
44-40-7200	< >	Under Body Ground Lights, Whelen 2G Super LED, Qty (6) Lights spaced three each side; one front of axle, one rear of axle, & one under rear bumper	1	PL
44-40-7800	< >	Under Body Ground Lights, Activation(when Equipped) Custom Chassis - Underbody ground lights shall activate as specified in the chassis specification. Commercial Chassis - Underbody ground lights to be activated with parking brake and marker lights. If the body has an entrance door, underbody ground lights will activate when door is open.	1	PL
12 VOLT FLOOD LIGHTS				PL
44-48-1000		12 Volt Flood Lights	1	PL
44-50-2220	<	Whelen M9 EZ Series LED Scene Lights, Chrome Flange, (2) On Rear Lights to include chrome flanges.	1	PL
44-50-6004	<	Whelen M9 EZ Series LED Scene Lights, Chrome Flange, (2) Per Side Lights to include chrome flanges.	1	PL
44-60-3200		Rear 12 Volt Flood Lights on w/Reverse	1	PL
44-60-7000		Left/Right Rearward Side Body 12 Volt Flood Lights, On In Reverse	1	PL
MULTIPLEXED FLOOD LIGHTS-GROUND LIGHTS (V-MUX)				PL
44-80-1000		Right Side Floods, V-MUX Multiplex screen controlled	1	PL
44-80-1100		Left Side Floods, V-MUX Multiplex screen controlled	1	PL
44-80-1200		Rear Floods, V-MUX Multiplex screen controlled	1	PL
EXTERIOR COMPARTMENT LIGHTS				PL
46-60-7900	<	Compartment Lighting, Amdor Luma Bar, White, Roll-Up Door Color: White	7	PL
MISCELLANEOUS 12 VOLT ELECTRICAL				PL
48-15-1550	<	Back-Up Camera ASA Voyager w/ 7" Rear View Mirror Replacement Monitor ASA Voyager System	1	PL

PART NO	S	DESCRIPTION	QTY	ID
		Standby/Manual switch located on the monitor		
		ELECTRICAL 120V SHORELINE		
51-20-4700	< >	Shoreline, Super Auto-Eject 20 amp, Body, Yellow Cover Location: Front Body	1	PL PL
51-20-8000		Shoreline power on indicator light	1	PL
		BATTERY CHARGER		
54-10-2000		Battery Charger, 45 amp	1	PL
		PAINT		
62-30-1600		Cab, Chassis manufacturers paint, no re-paint / no buff	1	PL
62-50-0000	< >	Paint body, Single color, with unpainted roll up doors Paint Color: Race Red FRD:11PQ	1	PL
62-50-1800	< >	Paint Rear Body Primary Color Only-(for Chevron Application) Note: Rear of vehicle to be painted, single primary color only (for Chevron Stripe application)	1	PL
62-65-109A	<	PL Poly Coat, Basic, Sides & Compartments Only, No Wheel Wells, 12'6", Red All lower exterior compartment floors, sills, and lower edge of body skin, excluding the front of the body. The coating on lower exterior compartments shall cover the welds of compartment floors and stop at a clean line 1/2" off the floor not to exceed the height of the Turtle Tile. Note: Standard stainless steel sills shall not be installed.	1	PL
62-80-5000		Paint and Finish Warranty	1	PL
62-80-5050		Paint Adhesion Testing	1	PL
		LETTERING		
64-70-1000	<	NO Lettering NO lettering is included with the vehicle.	1	PL
		REFLECTIVE STRIPING		
		CHEVRON STRIPING-(Reflective)		
65-50-3950	<	Reflexite 6" Chevron, Rear Body, No Doors, Red/Fluorescent Lime The two colors are V98 red 12 and V98 fluorescent lime 112. Note: Does not include any curved surfaces, such as the coves, or door trim.	1	PL PL PL
65-50-4100	<	Reflective striping on extending components When roll out trays, tool boards, or underbody compartments are included they will have reflective striping visible when the component is extended from the body. A reflective stripe will be fixed to the face and sides of the roll out tray. The color shall be red and white.	1	PL
65-50-7100	<	NFPA Reflective Chevron Panel, Interior Cab Door, (4)Door Aluminum panels will be added to the cab doors with reflective chevron stripe material. Chevron Colors: Red/Lime Yellow	1	PL
		ANTENNA LEAD(S)		
70-S1-1050	<	Antenna Base, Mount on Commercial Cab Roof Lead to Console Use with commercial chassis only. For units with custom chassis, antennas should be ordered installed by chassis manufacturer. Radio Information Sheet (see PDF associated with this line item) must be completed and sent in with order. Default location shall be lower cab roof. Maximum of (3) on Custom Cab.	1	PL PL

PART NO	S	DESCRIPTION	QTY	ID
		Antenna lead shall be unterminated.		
		MANUFACTURER SUPPLIED EQUIPMENT		
73-10-4000	< >	Wheel Chocks Zico (2) AC-32/QCH-32-H Horizontal bracket Location: Under Left Rear Body Skirt Behind Rear Wheel. Note: For light duty chassis only.	1	PL PL
73-60-1060	< >	NFPA Equipment Not Supplied In order to meet current NFPA requirements, the following equipment must be supplied and installed by the end user after delivery and before the vehicle is entered into service: (1) Automatic External Defibrillator (5) Traffic Cones with reflective bands (1) Case of traffic flares (8) Traffic vests meeting ANSI standards This equipment and mounting will not be part of the manufacturer's responsibility for delivery of the vehicle.	1	PL
		CHASSIS		
75-05-0100	U < >	Chassis, Custom Spec 2026 Ford F550 Ford F550 Chassis Crew Cab Four Wheel Drive Wheelbase 203" - 84" CA Dual Rear G.V.W. 19,500 lbs. Powertrain/Functional: Engine: 6.7L "Powerstroke" Turbo Diesel V8 300 hp @2800 RPM, 660 lbs torque @1600 RPM Single Stage Turbo Charger Instant Start Glow Plugs for quick engine starts Diesel Emissions Fluid 6 gallon tank - mounted behind frame rail on drivers side Intelligent Oil Life Monitor Engine block heater Water Pump with 125 gallons per minute flow rate Transmission: Heavy Duty "TorqShift" Ten Speed Automatic with selectable drive modes; Normal, Tow Haul, Eco, Deep Sand/Snow Electronic Shift on the Fly with automatic locking front hubs with manual override. Brakes - 4 wheel Anti-lock Braking System Traction Control - DRW Models Fuel Capacity: 40 gallon single tank (aft axle) Front Axle: 7,000 lb. Monobeam, Dana Super 60 Rear Axle: 14,706 lb. Full Floating Dana S110 Suspension: Heavy Duty Front Coil Springs Rear Leaf Springs, main & auxiliary Shock absorbers, front & rear 1.38" Stabilizer bar, front and rear Power Steering Steering Damper Instrumentation: multifunction switch message center - Gauges: Oil Pressure, Coolant Temperature, Trans Temp, w/Indicator Lights, Tachometer, Trip Odometer, Turbo boost, water in fuel warning light, low/contaminated diesel exhaust fluid warning lights, glow plug preheat indicator	1	PL

PART NO	S	DESCRIPTION	QTY	ID
		Ambulance Prep Package with EPA Special Emergency Vehicle Emissions - 47L Engine Calibration significantly reduces the possibility of depower mode when in stationary PTO mode Operator Commanded regen allowed down to 30% of DPF filter full instead of 100% Stationary elevated idle control (SEIC) is built into the engine control module Must meet definition of Emergency Vehicle; ambulance or fire truck in the federal register		
		Rear axle 4.30 Limited Slip Dual OEM HD Alternators (total 410 amps) 67B Dual 750 CCA Batteries Operated Commanded Regeneration (OCR) #98R		
		Safety/Security: Driver/Passenger frontal and side air bag/curtain Passenger side air bag deactivation switch Belt-Minder - chime & flashing warning light on instrument panel if belts not buckled Safety Belts - color coordinated with height adjustment (front outboard seating positions only) SOS Post-Crash Alert System Securi-lock Anti Theft Ignition		
		Tires: Front & Rear LT225/70R 19.5G All Position (6) #THB Spare Tire: LT225/70R 19.5G (All Position) Wheels; 10 hole Disc, 19.5" x 6" POLISHED ALUMINUM		
		Exterior Trim: Dual Electric Horns Chrome Front Bumper & Grille Surround Front Tow Hooks Lights - roof/marker clearance lights Dual Beam Jewel Effect Headlights High Mount Stop Light		
		Mirrors: Black POWER Telescoping Trailer Tow with Power Heated Glass, Integrated clearance lights, Turn signals, LED security approach lights, Utility lighting System (LED side mirror spotlights) #54F		
		XLT Interior Cab Trim: #663A Air Conditioning Cloth Headliner, Map Pockets AM/FM Radio w/ MP3		
		SYNC 4		
		4.2" LCD Productivity Screen in IP (Instrument Panel Cluster)		
		8" LCD Touchscreen with Swipe Capability in DASH		
		Outside Temperature Display Interval Windshield Wipers Tilt Steering Wheel/Speed Control - steering wheel mounted Power Windows/Door Locks Black Vinyl Floor (No Floor Mats) Headlights on audible alarm Dual overhead Map Light Daytime Running Lights Front seats, high series cloth - 40/20/40 #3S		
		Driver Assist Technology Audible Lane Departure Warning		

PART NO	S	DESCRIPTION	QTY	ID
		Pre-Collision Assist with Automatic Emergency Braking and forward collision warning		
		Automatic High Beam Headlights		
		Adjustable Pedals: gas and brake		
		Payload Upgrade Package		
		Trailer Tow Package		
		Color Scheme:		
		Exterior Color: Race Red (FRD:11PQ)		
		Interior Color: MEDIUM DARK SLATE		
CHASSIS MODIFICATIONS				
75-45-3550	>	Reserve Air Tank 5 Gallon	1	PL
75-60-5000	<	Insert, Aluminum, PL Poly Coat, Black, Cab Glass Replacement, F Series A 1/8 Aluminum Panel will replace the Rear Cab Glass. PL Black Poly Coat both Sides.	1	PL
75-90-8000		Chassis Preparation, component relocation	1	PL
75-90-8054		Fuel "Full Tank", Ford F-Series	1	PL
TERMS				
99-00-1500	S < >	Single Payment Terms Must be approved by factory and may incur additional cost.	1	PL
99-60-0000	S	END OF SPECIFICATIONS	1	PL